

**Responses to plan holder questions
Concrete Paver Walkway, Northwest Florida Regional Airport
April 17, 2015**

- 1. Relocating of palm trees: will the Owner pay for drip line irrigation at palms. If not will owner give allowance for additional drip lines, since contractor does not know where irrigations line will be located.**

Response: No new drip line irrigation shall be included in the contractor's bid. Note 4 on Sheet 2 will be revised in an addendum.

- 2. Electrical lite relocation: will contractor have to put in junction box for wire. If you have AS BUILT DRAWING or provide conduit location of existing line.**

Response: The Bid Documents will be revised to include the following language. "The contractor shall replace the existing electrical circuit, if needed, to ensure the circuit reaches the relocated lights and eliminates the need to include junction boxes for splices. All splices shall be located in the lighting fixtures or nearby street light poles and the contractor may utilize the existing conduits running under the existing sidewalk as shown on the plans. The contractor shall submit a shop drawing showing the location of the new circuit and tie-in points for approval by the Owner prior to making any electrical modifications."

- 3. Clarification of existing duct bank: Provide Drawing of duct bank as existing structure and will owner allow 6" PVC PIPE extension under sidewalk as conduit sleeve.**

Response: The Bid Documents will be revised to include the following language. "The required duct extensions shall match the existing non-concrete encased PVC duct diameter (estimated to be 3" PVC). Contractor shall properly bond the PVC duct extension to the existing PVC duct."

- 4. What are the hours of work and can we work on the weekends?**

Response: The Bid Documents will be revised to include the following language. "Hours of work shall be 7 am to 5 pm Monday through Sunday. The contractor shall schedule large material deliveries, such as base material and concrete pavers, during off-peak periods so deliveries do not adversely impact airport access. These schedules shall be submitted and approved by the Owner in advance. Contractor shall clearly identify construction areas and furnish construction barricades to prevent access into the construction area."

- 5. Bid Bond is this a requirement for submitting with our bid. We know Performance & Payment bonds are required if awarded the Contract.**

Please reference Addendum 2