



ADDENDUM 3

April 15, 2020

ITB FM 24-20

Repair, Inspection and Service of Fire Protection Equipment Components for Okaloosa County Facilities

This addendum is to provide the annual reports requested during the pre-bid meeting, and extend the time for question period.

See attached documents for annual reports.

The question deadline has been extended to April 23, 2020 at 3:00 P.M.

The ITB opening date remains May 6, 2020 at 3:15 P.M.

Report of Inspection/Test

Semi-Annual Sprinkler

10/05/2018

Property

Okaloosa County Health
 Department FWB NEW
 221 Hospital Dr.
 Fort Walton Beach, FL 32547

John Alfone
 (850)833-9240 x2255

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
 ALARMS - SPRINKLERS - EXTINGUISHERS

850-862-7812

Conducted by: Frank Sapp

Inspection Ref: 20000008248

Print Date: 4/14/2020

Signatures

Inspector - Printed Frank Sapp	Inspector - Signature <i>FS</i>	Date Completed 10/5/18	I state that the information on this form is correct at the time and place of my inspection, and that all equipment tested at this time was left in operational condition upon completion of this inspection except as noted.
-----------------------------------	------------------------------------	---------------------------	---

Tag Color

System Description/Location	Tag Color
Wet system	
Wet riser	Green

Notifications

To Be Notified	Testing Time	Phone Test	Contact / Operator
Security Central	Start Time: 08:00	800-286-5699	Jessica
	End Time: 09:00	800-286-5699	Dispatch
Okaloosa Dispatch	Start Time: 08:00	850-689-5766	Jennifer
	End Time: 09:00	850-689-5766	Patricia

Equipment Summary

Description	Site	Inspected		Unable to Inspect		Serviced Repaired		Failed	
	Qty	Qty	%	Qty	%	Qty	%	Qty	%
Sprinkler Valve									
OS&Y	2	2	100.0%	0	0.0%	0	0.0%	0	0.0%
Sprinkler Wet System Riser									
OS&Y	1	1	100.0%	0	0.0%	0	0.0%	0	0.0%

System Valve Inspection

Location/Description	Valve Description	Pressure Readings			Physical Condition	Pressures	Trim valves	Leakage	Hydraulic Sign	Valve Interior Inspection or Dry Valve Full Flow Test	
		Supply	System	Accelerator (if present)						Year Due	Inspection or Test Performed
Wet system											
Wet riser	4" Riser Check			NA	Ok	Ok	Ok	Ok	Ok		No

Print Date: 4/14/2020

Page 1 of 2

Report of Inspection/Test

Semi-Annual Sprinkler

10/05/2018

Property: Okaloosa County Health Department FWB NE1

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000008248

Pressure Gauge Inspection List

Qty	Location / Description	Condition Ok ?	Year Due for Replacement (5-Years)	Date Prior to Required Replacement ?	Quantity Replaced
Wet system					
1	Riser	Yes	2021	Yes	0

Fire Department Connection E Side of Bldg

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Flow Test

System	Connection Flowed	Outlet Size	Pressure (psi)			Time To Restore	Results comparable to prior test
			Static	Resid	Static		
Wet system							
Wet riser	Main drain	1/2	60	50	60	2	Yes

Inspector's Test Valve

System/Location	Alarm Reported	Time to Alarm	Smooth Bore Orifice	Signage	Easily Accessible
Wet system					
Wet riser	Yes	43	Yes	Yes	Yes

Valve Inspection List

Location / Description	Valve Type	Size	Secured	Inspection			
				Leakage	Open	Accessible	Signs
Wet system							
NA	NA	4"	NA	NA	NA	NA	NA
Backflow Supply	OS&Y	6"	Pad Locked	OK	OK	OK	NA
Backflow System Side	OS&Y	6"	Pad Locked	OK	OK	OK	NA

Ok - Passes Inspection S - Serviced on site X - Requires Service NA - Not Applicable

Print Date: 4/14/2020

Report of Inspection/Test

Annual Sprinkler

11/06/2019

Property

Okaloosa County Jail NEW

1200 East James Lee Blvd.
Crestview, FL 32539

Sgt. Denise
689-5690x1315

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS - SPRINKLERS - EXTINGUISHERS

850-862-7812

Conducted by: David Woodard

Inspection Ref: 200000010493

Print Date: 4/14/2020

Signatures

Inspector - Printed David Woodard	Inspector - Signature 	Date Completed 11/6/19	I state that the information on this form is correct at the time and place of my inspection, and that all equipment tested at this time was left in operational condition upon completion of this inspection except as noted.
--------------------------------------	---------------------------	---------------------------	---

Tag Color

System Description/Location	Tag Color								
Wet System									
Alpha Pod/ transport office	Red Critical								
Admin / Medical	Green								
Bravo Pod	Red Critical								
Charlie Pod	Green								
Echo Pod	Red Critical								
Delta Pod	Green								
Dry System									
Sally Port	Red Critical								
No system pressure switch Air compressor would not activate									
Delta Pod	Green								
Okaloosa	<table border="1"> <tr> <td>Start Time:</td> <td>8:15</td> <td>850-689-5766</td> <td>Heather</td> </tr> <tr> <td>End Time:</td> <td>2:30</td> <td>850-689-5766</td> <td>Jennifer</td> </tr> </table>	Start Time:	8:15	850-689-5766	Heather	End Time:	2:30	850-689-5766	Jennifer
Start Time:	8:15	850-689-5766	Heather						
End Time:	2:30	850-689-5766	Jennifer						

Equipment Summary

Description	Site	Inspected		Unable to Inspect		Served Repaired		Failed		
	Qty	Qty	%	Qty	%	Qty	%	Qty	%	
Sprinkler Dry System Riser										
Main drain	1	1	100.0%	0	0.0%	0	0.0%	0	0.0%	
OS&Y	1	1	100.0%	0	0.0%	0	0.0%	0	0.0%	
Sprinkler Valve										
OS&Y	3	3	100.0%	0	0.0%	0	0.0%	0	0.0%	
Sprinkler Wet System Riser										
Main drain	5	5	100.0%	0	0.0%	0	0.0%	0	0.0%	
Butterfly	1	1	100.0%	0	0.0%	0	0.0%	0	0.0%	

System Valve Inspection

Print Date: 4/14/2020

Page 1 of 8

Report of Inspection/Test

Annual Sprinkler

11/06/2019

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000010493

System Valve Inspection

Location/Description	Valve Description	Pressure Readings			Physical Condition	Pressures	Trim valves	Leakage	Hydraulic Sign	Valve Interior Inspection or Dry Valve Full Flow Test	
		Supply	System	Accelerator (if present)						Year Due	Inspection or Test Performed
Wet System											
Alpha Pod/ transport office	4" Riser Check 1984 Victaulic 80		90	NA	Ok	Ok	Ok	Ok	Ok	2020	No
Admin / Medical	4"		90	NA	Ok	Ok	NA	Ok	Ok	2020	No
Bravo Pod	4"		90	NA	Ok	Ok	NA	Ok	Ok	2020	No
Charlie Pod	4"		85	NA	Ok	Ok	NA	Ok	Ok	2020	No
Echo Pod	4"		90	NA	Ok	Ok	NA	Ok	Ok	2020	No
Delta Pod	4" Riser Check B		90	NA	Ok	Ok	NA	Ok	Ok	2020	No

Fire Sprinklers

Sprinkler Type	Manufacturer Model	K Factor Temperature	Thread Size	Year of Manufacture	Year Replace or Testing Required	Replace Test or Recall Req Ok ?	Spare Sprinkler Available	Wrench Available
Std Upright Chrome	Tyco TY323	5.6/155	1/2"			Yes	Yes	Yes
Std Pendent Chrome	Tyco TY3281 INST	5.6/155	1/2"			Yes	Yes	Yes
QR Sidewall Chrome	Tyco TY3390	5.6/155	1/2"			Yes	Yes	Yes
Std Sidewall Brass	Central SOLDER L	5.6/155	1/2"			Yes	Yes	Yes
QR Sidewall Chrome	RASCO R3731	5.6/165	1/2"			Yes	Yes	Yes
QR Sidewall Brass	Tyco TY3331	200	1/2"			Yes	Yes	Yes
QR Upright brass	Tyco TY3131	5.6/155	1/2"			Yes	Yes	Yes
QR Upright Chrome	Central	200	1/2"			Yes	Yes	Yes

Report of Inspection/Test

Annual Sprinkler

11/06/2019

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000010493

Pressure Gauge Inspection List

Qty	Location / Description	Condition Ok ?	Year Due for Replacement (5-Years)	Date Prior to Required Replacement ?	Quantity Replaced
Wet System					
1	Alpha Pod/ transport office	Yes	2020	Yes	0
1	Admin / Medical	Yes	2020	Yes	0
1	Bravo Pod	Yes	2020	Yes	0
1	Charlie Pod	Yes	2020	Yes	0
1	Echo Pod	Yes	2020	Yes	0
1	Delta Pod	Yes	2020	Yes	0
Dry System					
2	Sally Port	Yes	2023	Yes	0
2	Delta Pod	Yes	2020	Yes	0

Long Cycle Items

Item Type	Location/Description	Required Frequency	Last Performed	Next Due
Riser	All	Every 5 years	2015	2020

Pipe				
Yes	In good condition ?	Yes	Free of mechanical damage and not leaking ?	
Yes	No external corrosion ?	Yes	Properly aligned ?	
Yes	No external loads ?	Yes	Visible pipe hangers and seismic braces not damaged or loose ?	

Sprinklers				
NA	Extra high, very extra high and ultra high temperature sprinklers tested ?	No	Eng evaluation recommended for spacing?	
No	Eng evaluation recommended for sprinkler type?	Yes	Proper number and type of spare sprinklers?	
No	Free of corrosion?	Yes	Free of obstructions to spray patterns?	
Found corroded sprinkler heads				
No	Free of foreign materials including paint?	No	Free of physical damage?	
Found painted sprinkler heads				
Yes	Sprinklers free of loading and dirt?	Yes	Escutcheons and coverplates for recessed, flush and concealed sprinklers not missing?	
Yes	Are all sprinklers in service dated 1920 or later?	Yes	Fast Response sprinklers in service for less than 20 years? If no test sample now and every 10 years.	
Yes	Standard sprinklers less than 50 years old ? If no test sample now and every 10 years.	NA	If sprinklers have been replaced, were they proper replacements?	

Fire Department Connection Alpha				
Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?	
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?	
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?	
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?	
NA	Valve clapper operational over its full range (if caps are not in place) ?			

Print Date: 4/14/2020

Page 3 of 8

Report of Inspection/Test

Annual Sprinkler

11/06/2019

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000010493

Fire Department Connection Admin / Medical

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Fire Department Connection Bravo

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Fire Department Connection Charlie

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Fire Department Connection Echo

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Air Compressor PIPE MOUNT SallyPort Dry System

GENERAL	Manufacturer of compressor	DL161-5035	Model of compressor
ELECTRIC			
3/4	Size of compressor (HP)	PIPE MOUNT	Compressor Description/Type
No	Compressor appears to be in working condition?	NA	Compressor appears free of leaks?
NA	Compressor and motor are free of vibration and unusual noises?	NA	Guages appear Ok and show normal PSI
NA	Oil appears clean with no burnt odor	No	Electrical connections Ok?
NA	Breaker in the ON Position?	NA	Inlet air filter clean?
NA	Belt is in good condition?	NA	Tension on the belt is Ok?
NA	Has condensate/water been drained from the tank and/or water separator?	NA	Dryer/Separator Ok?

Cold Weather Check Sally Port Dry System

NA	Adequate heat in areas with wet piping?	NA	Low temperature alarms in dry pipe, preaction and deluge valve enclosures functioning?
NA	Interior of pipe in preaction and dry pipe systems which passes through freezers free of ice blockage?	NA	Low points drained in dry pipe, preaction and deluge systems prior to the onset of freezing weather?

Print Date: 4/14/2020

Page 4 of 8

Report of Inspection/Test

Annual Sprinkler

11/06/2019

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000010493

Air Compressor Delta floor mounted tank

General Electric	Manufacturer of compressor	9QK56C17D2012	Model of compressor
		P	
1/2	Size of compressor (HP)	floor mounted tank	Compressor Description/Type
Yes	Compressor appears to be in working condition?	Yes	Compressor appears free of leaks?
Yes	Compressor and motor are free of vibration and unusual noises?	NA	Guages appear Ok and show normal PSI
NA	Oil appears clean with no burnt odor	Yes	Electrical connections Ok?
Yes	Breaker in the ON Position?	NA	Inlet air filter clean?
NA	Belt is in good condition?	NA	Tension on the belt is Ok?
NA	Has condensate/water been drained from the tank and/or water separator?	NA	Dryer/Separator Ok?

Cold Weather Check Delta Pod Dry System

NA	Adequate heat in areas with wet piping?	NA	Low temperature alarms in dry pipe, preaction and deluge valve enclosures functioning?
NA	Interior of pipe in preaction and dry pipe systems which passes through freezers free of ice blockage?	NA	Low points drained in dry pipe, preaction and deluge systems prior to the onset of freezing weather?

Fire Department Connection Delta

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Flow Test

System	Connection Flowed	Outlet Size	Pressure (psi)			Time To Restore	Results comparable to prior test
			Static	Resid	Static		
Wet System							
Alpha Pod/ transport office	Main drain	2	90	70	90	5	Yes
Admin / Medical	Main drain	2	90	75	90	5	Yes
Bravo Pod	Main drain	2	90	75	90	5	Yes
Charlie Pod	Main drain	2	85	70	85	5	Yes
Echo Pod	Main drain	2	90	75	90	5	Yes
Delta Pod	Main drain	2	90	75	90	5	Yes
Dry System							
Sally Port	Main drain	2					
Delta Pod	Main drain	2	90	75	90	5	Yes

Report of Inspection/Test

Annual Sprinkler

11/06/2019

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000010493

Inspector's Test Valve

System/Location	Alarm Reported	Time to Alarm	Smooth Bore Orifice	Signage	Easily Accessible
Wet System					
Alpha Pod/ transport office	Yes	8	Yes	Yes	Yes
Admin / Medical	Yes	50	Yes	Yes	Yes
Bravo Pod	Yes	20	Yes	Yes	Yes
Charlie Pod	Yes	25	Yes	Yes	Yes
Echo Pod	Yes	45	Yes	Yes	Yes
Delta Pod	Yes	45	Yes	Yes	Yes
Dry System					
Sally Port	NA	NA	NA	NA	NA
Delta Pod	Yes	1	Yes	Yes	Yes

Valve Inspection List

Location	Valve Type	Size	Secured	Inspection				Maint.			
				Leakage	Open	Accessible	Signs	Exercised	# of Turns	Lubricated	
Backflow Supply	OS&Y	6"	Pad Locked	Ok	Ok	Ok	Ok	Ok	Ok	20	NA
Backflow Supply delta pod	OS&Y	4"	Pad Locked	Ok	Ok	Ok	NA	Ok	Ok	14	NA
Backflow System Side	OS&Y	4"	Pad Locked	Ok	Ok	Ok	NA	Ok	Ok	14	NA

Backflow

Backflow System Side	OS&Y	6"	Pad Locked	Ok	Ok	Ok	Ok	Ok	Ok	20	NA
----------------------	------	----	------------	----	----	----	----	----	----	----	----

Wet System

Alpha Pod/ transport office	OS&Y	2"	Supervised	Ok	Ok	Ok	Ok	Ok	Ok	10	NA
Admin / Medical	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok	Ok	Ok	14	NA
Bravo Pod	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok	Ok	Ok	14	NA
Charlie Pod	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok	Ok	Ok	14	NA
Echo Pod	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok	Ok	Ok	14	NA
Delta Pod	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok	Ok	Ok	14	NA

Dry System

Sally Port	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok	Ok	Ok	14	NA
Delta Pod	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok	Ok	Ok	14	NA

Ok - Passes Inspection S - Serviced on site X - Requires Service NA - Not Applicable

Dry Valve Trip Test - Dry System

Print Date: 4/14/2020

Page 6 of 8

Report of Inspection/Test

Annual Sprinkler

11/06/2019

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000010493

Dry Valve		Size: 4"	Year: 01/01/00	Q. O. D.		Year:
Make	Model	Serial no.		Make	Model	Serial no.
	Time to Trip thru test pipe	Water Pressure	Air Pressure	Trip point air pressure	Time water reached test outlet	Alarm Operated
Without Q.O.D.	sec	psi	psi	psi	sec	
With Q.O.D.	sec	psi	psi	psi	sec	

Comparable to previous tests ?

Dry Valve		Size: 4"	Year: 01/01/00	Q. O. D.		Year:
Make	Model	Serial no.		Make	Model	Serial no.
	Time to Trip thru test pipe	Water Pressure	Air Pressure	Trip point air pressure	Time water reached test outlet	Alarm Operated
Without Q.O.D.	sec	psi	psi	psi	sec	
With Q.O.D.	sec	psi	psi	psi	sec	

Comparable to previous tests ?

Report of Inspection/Test

Annual Sprinkler

11/06/2019

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000010493

Deficiency / Recommendations Summary

These items were deficient and do not meet the requirements of the applicable code at the time of the inspection. Items marked *Recommendation* are not required by the applicable code but are opportunities to improve the Life Safety of the property.

Sprinklers All

Inspection Riser All

No Free of corrosion?

Found corroded sprinkler heads

NFPA-25-2011 5.2.1.1 *Sprinklers shall be inspected from the floor level annually.*

No Free of foreign materials including paint?

Found painted sprinkler heads

NFPA-25-2011 5.2.1.1 *Sprinklers shall be inspected from the floor level annually.*

No Free of physical damage?

Found damaged sprinkler heads

NFPA-25-2011 5.2.1.1 *Sprinklers shall be inspected from the floor level annually.*

Air Compressor PIPE MOUNT SallyPort Dry System

GENERAL ELECTRIC DL161-5035 Compressor

No Compressor appears to be in working condition?

No Electrical connections Ok?

Tag Sally Port Dry System Sally Port

Dry System Riser OS&Y Sally Port

Red Critical Tag Color

No system pressure switch

Air compressor would not activate

Report of Inspection/Test

Quarterly Sprinkler

01/31/2018

Property

Okaloosa County Jail NEW

1200 East James Lee Blvd.
Crestview, FL 32539

Sgt. Denise
689-5690x1315

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS - SPRINKLERS - EXTINGUISHERS

850-862-7812

Conducted by: Frank Sapp

Inspection Ref: 20000006306

Print Date: 4/14/2020

Signatures

Inspector - Printed Frank Sapp	Inspector - Signature <i>Frank Sapp</i>	Date Completed 2/2/18	I state that the information on this form is correct at the time and place of my inspection, and that all equipment tested at this time was left in operational condition upon completion of this inspection except as noted.
-----------------------------------	--	--------------------------	---

Tag Color

System Description/Location	Tag Color
Admin / Medical	
Admin / Medical	Green
Bravo pod	
Bravo Pod	Green
Alpha Pod	
Alpha Pod/ transport office	Green
Echo	
Echo Pod	Green
Delta	
Delta Pod	Green
Charlie	
Charlie Pod	Green
Delta	
Delta Pod	Green
Sally Port	
Sally Port	Green

Notifications

To Be Notified	Testing Time	Phone Test	Contact / Operator
Building Management	Start Time:		
	End Time:		

Equipment Summary

Description	Site	Inspected		Unable to Inspect		Serviced Repaired		Failed	
	Qty	Qty	%	Qty	%	Qty	%	Qty	%

Print Date: 4/14/2020

Page 1 of 8

Report of Inspection/Test

Quarterly Sprinkler

01/31/2018

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000006306

Equipment Summary

Description	Site	Inspected		Unable to Inspect		Serviced Repaired		Failed	
	Qty	Qty	%	Qty	%	Qty	%	Qty	%
Sprinkler Dry System Riser									
Main drain	1	1	100.0%	0	0.0%	0	0.0%	1	100.0%
OS&Y	1	1	100.0%	0	0.0%	0	0.0%	1	100.0%
Sprinkler Valve									
OS&Y	4	4	100.0%	0	0.0%	0	0.0%	0	0.0%
Sprinkler Wet System Riser									
Main drain	5	5	100.0%	0	0.0%	0	0.0%	0	0.0%
Butterfly	1	1	100.0%	0	0.0%	0	0.0%	0	0.0%

System Valve Inspection

Location/Description	Valve Description	Pressure Readings			Physical Condition	Pressures	Trim valves	Leakage	Hydraulic Sign	Valve Interior Inspection or Dry Valve Full Flow Test	
		Supply	System	Accelerator (if present)						Year Due	Inspection or Test Performed
Admin / Medical											
Admin / Medical				NA	NA	NA	NA	NA	NA		NA
Bravo pod											
Bravo Pod	NA			NA	NA	NA	NA	NA	NA		NA
Alpha Pod											
Alpha Pod/ transport office	Alarm Victaulic 80			NA	Ok	Ok	Ok	Ok	Ok		No
Echo											
Echo Pod											
Charlie											
Charlie Pod											
Delta											
Delta Pod	NA B			NA	NA	NA	NA	NA	NA		NA

Report of Inspection/Test

Quarterly Sprinkler

01/31/2018

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000006306

Fire Sprinklers

Sprinkler Type	Manufacturer Model	K Factor Temperature	Thread Size	Year of Manufacture	Year Replace or Testing Required	Replace Test or Recall Req Ok ?	Spare Sprinkler Available	Wrench Available
Std Upright	Tyco TY323 CH	5.6/155	1/2"			Yes	Yes	Yes
Std Pendent	Tyco TY3281 INST	5.6/155	1/2"			Yes	Yes	Yes
QR Sidewall	Tyco TY3390 CH	5.6/155	1/2"			Yes	Yes	Yes
QR Sidewall	RASCO R3731 CH	5.6/165	1/2"			Yes	Yes	Yes
QR Sidewall	Tyco TY3331 BR	200	1/2"			Yes	Yes	Yes
Std Sidewall	Central SOLDER L	5.6/155	1/2"			Yes	Yes	Yes
QR Upright	Tyco TY3131 BRAS	5.6/155	1/2"			Yes	Yes	Yes
QR Upright	Central UNKNOW	200	1/2"			Yes	Yes	Yes

Pressure Gauge Inspection List

Qty	Location / Description	Condition Ok ?	Year Due for Replacement (5-Years)	Date Prior to Required Replacement ?	Quantity Replaced
Admin / Medical					
1	Riser	Yes	2019	Yes	0
Bravo pod					
1	Riser	Yes	2020	Yes	0
Alpha Pod					
1	Training office	Yes	2020	Yes	0
Echo					
1	Riser	Yes	2020	Yes	0
Delta					
1	Riser	Yes	2020	Yes	0
Charlie					
1					
Delta					
2	Riser	Yes	2020	Yes	0
Sally Port					
2	Riser	Yes	2022	Yes	0
Fire Department Connection Alpha					
Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?		
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?		
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?		
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?		

Print Date: 4/14/2020

Page 3 of 8

Report of Inspection/Test

Quarterly Sprinkler

01/31/2018

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000006306

Fire Department Connection Alpha

NA Valve clapper operational over its full range (if caps are not in place) ?

Fire Department Connection Admin / Medical

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Fire Department Connection Bravo

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Fire Department Connection Charlie

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Fire Department Connection Echo

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Air Compressor PIPE MOUNT

GENERAL	Manufacturer of compressor	DL161-5035	Model of compressor
ELECTRIC			
3/4	Size of compressor (HP)	PIPE MOUNT	Compressor Description/Type
Yes	Compressor appears to be in working condition?	Yes	Compressor appears free of leaks?
Yes	Compressor and motor are free of vibration and unusual noises?	Yes	Guages appear Ok and show normal PSI
NA	Oil appears clean with no burnt odor	Yes	Electrical connections Ok?
Yes	Breaker in the ON Postion?	Yes	Inlet air filter clean?
NA	Belt is in good condition?	NA	Tension on the belt is Ok?
NA	Has condensate/water been drained from the tank and/or water separator?	NA	Dryer/Separator Ok?

Report of Inspection/Test

Quarterly Sprinkler

01/31/2018

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000006306

Dry Pipe Valve Inspection Sally Port

Yes	Enclosures around dry-pipe, preaction or deluge valves maintaining a minimum of 40deg F?	Yes	Gauges on dry, preaction and deluge systems in good condition and showing normal air and water pressure?
Yes	Free from physical damage?	Yes	Trim valves in appropriate (open or closed) position?
Yes	No leakage from intermediate chamber?	Yes	Priming water level correct?
NA	Low air pressure signal passed test?	NA	Quick opening devices passed test?

Air Compressor floor mounted tank

General Electric	Manufacturer of compressor	9QK56C17D2012	Model of compressor
1/2	Size of compressor (HP)	P floor mounted tank	Compressor Description/Type
Yes	Compressor appears to be in working condition?	Yes	Compressor appears free of leaks?
Yes	Compressor and motor are free of vibration and unusual noises?	Yes	Guages appear Ok and show normal PSI
Yes	Oil appears clean with no burnt odor	Yes	Electrical connections Ok?
Yes	Breaker in the ON Position?	Yes	Inlet air filter clean?
Yes	Belt is in good condition?	Yes	Tension on the belt is Ok?
NA	Has condensate/water been drained from the tank and/or water separator?	NA	Dryer/Separator Ok?

Dry Pipe Valve Inspection Delta

Yes	Enclosures around dry-pipe, preaction or deluge valves maintaining a minimum of 40deg F?	Yes	Gauges on dry, preaction and deluge systems in good condition and showing normal air and water pressure?
Yes	Free from physical damage?	Yes	Trim valves in appropriate (open or closed) position?
Yes	No leakage from intermediate chamber?	Yes	Priming water level correct?
Yes	Low air pressure signal passed test?	Yes	Quick opening devices passed test?

Fire Department Connection Delta

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Flow Test

System	Connection Flowed	Outlet Size	Pressure (psi)			Time To Restore	Results comparable to prior test
			Static	Resid	Static		
Admin / Medical							
Admin / Medical	Main drain	2	60	45	60	2	Yes
Bravo pod							
Bravo Pod	Main drain	2	90	60	90	2	Yes
Alpha Pod							
Alpha Pod/ transport office	Main drain	2	90	60	90	2	Yes
Echo							
Echo Pod	Main drain	2	90	60	90	2	Yes

Print Date: 4/14/2020

Page 5 of 8

Report of Inspection/Test

Quarterly Sprinkler

01/31/2018

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000006306

Flow Test

System	Connection Flowed	Outlet Size	Pressure (psi)			Time To Restore	Results comparable to prior test
			Static	Resid	Static		
Charlie							
Charlie Pod	Main drain	2	90	60	90	2	Yes
Delta							
Delta Pod	Main drain	2	90	60	90	2	Yes
Delta Pod	Main drain	2	90	60	90	2	Yes
SYSTEM IS CONTROLLED BY ADMIN/MEDICAL IN CHARLIE POD CLOSET. DRAIN IS NOT PIPED OUT OF ROOM 2 INCH VALVE ONL							
Sally Port							
Sally Port	Outlet not piped out						NA

Inspector's Test Valve

System/Location	Alarm Reported	Time to Alarm	Smooth Bore Orifice	Signage	Easily Accessible
Admin / Medical					
Admin / Medical	Yes	NA	Yes	Yes	Yes
Bravo pod					
Bravo Pod	NA	NA	Yes	Yes	Yes
Alpha Pod					
Alpha Pod/ transport office	Yes		Yes	Yes	Yes
Echo					
Echo Pod	NA	NA	Yes	Yes	Yes
Delta					
Delta Pod	NA	NA	Yes	Yes	Yes
Charlie					
Charlie Pod	NA	NA	Yes	Yes	Yes
Delta					
Delta Pod	No	NA	Yes	Yes	Yes
Sally Port					
Sally Port	NA	NA	Yes	Yes	No
NEED PIPED DOWN TO HEAD HIGH					

Valve Inspection List

Location / Description	Valve Type	Size	Secured	Inspection			
				Leakage	Open	Accessible	Signs

Report of Inspection/Test

Quarterly Sprinkler

01/31/2018

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000006306

Valve Inspection List

Location / Description	Valve Type	Size	Secured	Inspection			
				Leakage	Open	Accessible	Signs
Backflow Supply delta pod	Control	4"	Pad Locked	Ok	Ok	Ok	Ok
Backflow System Side	Control	4"	Pad Locked	Ok	Ok	Ok	Ok
Backflow Supply	Control	6"	Pad Locked	Ok	Ok	Ok	Ok
Backflow System Side	Control	6"	Pad Locked	Ok	Ok	Ok	Ok
Admin / Medical							
Admin-Medical	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok
Bravo pod							
Bravo.-Charlie pod closet	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok
Alpha Pod							
Riser Training office	Butterfly	4"	Supervised	Ok	Ok	Ok	Ok
Echo							
Echo-Charlie pod closet	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok
Charlie							
Charlie in Charlie closet	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok
Delta							
Delta- Charlie pod closet	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok
riser	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok
Sally Port							
Sally port Bus closet	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok
Ok - Passes Inspection S - Serviced on site X - Requires Service NA - Not Applicable							

Report of Inspection/Test

Quarterly Sprinkler

01/31/2018

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000006306

Deficiency / Recommendations Summary

These items were deficient and do not meet the requirements of the applicable code at the time of the inspection. Items marked *Recommendation* are not required by the applicable code but are opportunities to improve the Life Safety of the property.

Flow Test Delta Delta Pod

Central Dry System Riser Main drain Delta Pod

DELTA System/Location

MAINTENANCE

CHASE

SYSTEM IS CONTROLLED BY ADMIN/MEDICAL IN CHARLIE POD CLOSET. DRAIN IS NOT PIPED OUT OF ROOM 2 INCH VALVE ONL

Inspector's Test Valve Delta Delta Pod

Central Dry System Riser Main drain Delta Pod

No Alarm Reported?

Inspector's Test Valve Sally Port Sally Port

Dry System Riser OS&Y Sally Port

No Easily accessible?

NEED PIPED DOWN TO HEAD HIGH

Report of Inspection/Test

Quarterly Sprinkler

01/31/2018

Property

Okaloosa County Jail NEW

1200 East James Lee Blvd.
Crestview, FL 32539

Sgt. Denise
689-5690x1315

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS - SPRINKLERS - EXTINGUISHERS

850-862-7812

Conducted by: Frank Sapp

Inspection Ref: 20000006306

Print Date: 4/14/2020

Signatures

Inspector - Printed Frank Sapp	Inspector - Signature <i>Frank Sapp</i>	Date Completed 2/2/18	I state that the information on this form is correct at the time and place of my inspection, and that all equipment tested at this time was left in operational condition upon completion of this inspection except as noted.
-----------------------------------	--	--------------------------	---

Tag Color

System Description/Location	Tag Color
Admin / Medical	
Admin / Medical	Green
Bravo pod	
Bravo Pod	Green
Alpha Pod	
Alpha Pod/ transport office	Green
Echo	
Echo Pod	Green
Delta	
Delta Pod	Green
Charlie	
Charlie Pod	Green
Delta	
Delta Pod	Green
Sally Port	
Sally Port	Green

Notifications

To Be Notified	Testing Time	Phone Test	Contact / Operator
Building Management	Start Time:		
	End Time:		

Equipment Summary

Description	Site	Inspected		Unable to Inspect		Serviced Repaired		Failed	
	Qty	Qty	%	Qty	%	Qty	%	Qty	%

Print Date: 4/14/2020

Page 1 of 8

Report of Inspection/Test

Quarterly Sprinkler

01/31/2018

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000006306

Equipment Summary

Description	Site	Inspected		Unable to Inspect		Serviced Repaired		Failed	
	Qty	Qty	%	Qty	%	Qty	%	Qty	%
Sprinkler Dry System Riser									
Main drain	1	1	100.0%	0	0.0%	0	0.0%	1	100.0%
OS&Y	1	1	100.0%	0	0.0%	0	0.0%	1	100.0%
Sprinkler Valve									
OS&Y	4	4	100.0%	0	0.0%	0	0.0%	0	0.0%
Sprinkler Wet System Riser									
Main drain	5	5	100.0%	0	0.0%	0	0.0%	0	0.0%
Butterfly	1	1	100.0%	0	0.0%	0	0.0%	0	0.0%

System Valve Inspection

Location/Description	Valve Description	Pressure Readings			Physical Condition	Pressures	Trim valves	Leakage	Hydraulic Sign	Valve Interior Inspection or Dry Valve Full Flow Test	
		Supply	System	Accelerator (if present)						Year Due	Inspection or Test Performed
Admin / Medical											
Admin / Medical				NA	NA	NA	NA	NA	NA		NA
Bravo pod											
Bravo Pod	NA			NA	NA	NA	NA	NA	NA		NA
Alpha Pod											
Alpha Pod/ transport office	Alarm Victaulic 80			NA	Ok	Ok	Ok	Ok	Ok		No
Echo											
Echo Pod											
Charlie											
Charlie Pod											
Delta											
Delta Pod	NA B			NA	NA	NA	NA	NA	NA		NA

Report of Inspection/Test

Quarterly Sprinkler

01/31/2018

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000006306

Fire Sprinklers

Sprinkler Type	Manufacturer Model	K Factor Temperature	Thread Size	Year of Manufacture	Year Replace or Testing Required	Replace Test or Recall Req Ok ?	Spare Sprinkler Available	Wrench Available
Std Upright	Tyco TY323 CH	5.6/155	1/2"			Yes	Yes	Yes
Std Pendent	Tyco TY3281 INST	5.6/155	1/2"			Yes	Yes	Yes
QR Sidewall	Tyco TY3390 CH	5.6/155	1/2"			Yes	Yes	Yes
QR Sidewall	RASCO R3731 CH	5.6/165	1/2"			Yes	Yes	Yes
QR Sidewall	Tyco TY3331 BR	200	1/2"			Yes	Yes	Yes
Std Sidewall	Central SOLDER L	5.6/155	1/2"			Yes	Yes	Yes
QR Upright	Tyco TY3131 BRAS	5.6/155	1/2"			Yes	Yes	Yes
QR Upright	Central UNKNOW	200	1/2"			Yes	Yes	Yes

Pressure Gauge Inspection List

Qty	Location / Description	Condition Ok ?	Year Due for Replacement (5-Years)	Date Prior to Required Replacement ?	Quantity Replaced
Admin / Medical					
1	Riser	Yes	2019	Yes	0
Bravo pod					
1	Riser	Yes	2020	Yes	0
Alpha Pod					
1	Training office	Yes	2020	Yes	0
Echo					
1	Riser	Yes	2020	Yes	0
Delta					
1	Riser	Yes	2020	Yes	0
Charlie					
1					
Delta					
2	Riser	Yes	2020	Yes	0
Sally Port					
2	Riser	Yes	2022	Yes	0

Fire Department Connection Alpha

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?

Print Date: 4/14/2020

Page 3 of 8

Report of Inspection/Test

Quarterly Sprinkler

01/31/2018

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000006306

Fire Department Connection Alpha

NA Valve clapper operational over its full range (if caps are not in place) ?

Fire Department Connection Admin / Medical

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Fire Department Connection Bravo

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Fire Department Connection Charlie

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Fire Department Connection Echo

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Air Compressor PIPE MOUNT

GENERAL	Manufacturer of compressor	DL161-5035	Model of compressor
ELECTRIC			
3/4	Size of compressor (HP)	PIPE MOUNT	Compressor Description/Type
Yes	Compressor appears to be in working condition?	Yes	Compressor appears free of leaks?
Yes	Compressor and motor are free of vibration and unusual noises?	Yes	Guages appear Ok and show normal PSI
NA	Oil appears clean with no burnt odor	Yes	Electrical connections Ok?
Yes	Breaker in the ON Postion?	Yes	Inlet air filter clean?
NA	Belt is in good condition?	NA	Tension on the belt is Ok?
NA	Has condensate/water been drained from the tank and/or water separator?	NA	Dryer/Separator Ok?

Report of Inspection/Test

Quarterly Sprinkler

01/31/2018

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000006306

Dry Pipe Valve Inspection Sally Port

Yes	Enclosures around dry-pipe, preaction or deluge valves maintaining a minimum of 40deg F?	Yes	Gauges on dry, preaction and deluge systems in good condition and showing normal air and water pressure?
Yes	Free from physical damage?	Yes	Trim valves in appropriate (open or closed) position?
Yes	No leakage from intermediate chamber?	Yes	Priming water level correct?
NA	Low air pressure signal passed test?	NA	Quick opening devices passed test?

Air Compressor floor mounted tank

General Electric	Manufacturer of compressor	9QK56C17D2012	Model of compressor
1/2	Size of compressor (HP)	P floor mounted tank	Compressor Description/Type
Yes	Compressor appears to be in working condition?	Yes	Compressor appears free of leaks?
Yes	Compressor and motor are free of vibration and unusual noises?	Yes	Guages appear Ok and show normal PSI
Yes	Oil appears clean with no burnt odor	Yes	Electrical connections Ok?
Yes	Breaker in the ON Position?	Yes	Inlet air filter clean?
Yes	Belt is in good condition?	Yes	Tension on the belt is Ok?
NA	Has condensate/water been drained from the tank and/or water separator?	NA	Dryer/Separator Ok?

Dry Pipe Valve Inspection Delta

Yes	Enclosures around dry-pipe, preaction or deluge valves maintaining a minimum of 40deg F?	Yes	Gauges on dry, preaction and deluge systems in good condition and showing normal air and water pressure?
Yes	Free from physical damage?	Yes	Trim valves in appropriate (open or closed) position?
Yes	No leakage from intermediate chamber?	Yes	Priming water level correct?
Yes	Low air pressure signal passed test?	Yes	Quick opening devices passed test?

Fire Department Connection Delta

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Flow Test

System	Connection Flowed	Outlet Size	Pressure (psi)			Time To Restore	Results comparable to prior test
			Static	Resid	Static		
Admin / Medical							
Admin / Medical	Main drain	2	60	45	60	2	Yes
Bravo pod							
Bravo Pod	Main drain	2	90	60	90	2	Yes
Alpha Pod							
Alpha Pod/ transport office	Main drain	2	90	60	90	2	Yes
Echo							
Echo Pod	Main drain	2	90	60	90	2	Yes

Print Date: 4/14/2020

Page 5 of 8

Report of Inspection/Test

Quarterly Sprinkler

01/31/2018

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000006306

Flow Test

System	Connection Flowed	Outlet Size	Pressure (psi)			Time To Restore	Results comparable to prior test
			Static	Resid	Static		
Charlie							
Charlie Pod	Main drain	2	90	60	90	2	Yes
Delta							
Delta Pod	Main drain	2	90	60	90	2	Yes
Delta Pod	Main drain	2	90	60	90	2	Yes
SYSTEM IS CONTROLLED BY ADMIN/MEDICAL IN CHARLIE POD CLOSET. DRAIN IS NOT PIPED OUT OF ROOM 2 INCH VALVE ONL							
Sally Port							
Sally Port	Outlet not piped out						NA

Inspector's Test Valve

System/Location	Alarm Reported	Time to Alarm	Smooth Bore Orifice	Signage	Easily Accessible
Admin / Medical					
Admin / Medical	Yes	NA	Yes	Yes	Yes
Bravo pod					
Bravo Pod	NA	NA	Yes	Yes	Yes
Alpha Pod					
Alpha Pod/ transport office	Yes		Yes	Yes	Yes
Echo					
Echo Pod	NA	NA	Yes	Yes	Yes
Delta					
Delta Pod	NA	NA	Yes	Yes	Yes
Charlie					
Charlie Pod	NA	NA	Yes	Yes	Yes
Delta					
Delta Pod	No	NA	Yes	Yes	Yes
Sally Port					
Sally Port	NA	NA	Yes	Yes	No
NEED PIPED DOWN TO HEAD HIGH					

Valve Inspection List

Location / Description	Valve Type	Size	Secured	Inspection			
				Leakage	Open	Accessible	Signs

Report of Inspection/Test

Quarterly Sprinkler

01/31/2018

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000006306

Valve Inspection List

Location / Description	Valve Type	Size	Secured	Inspection			
				Leakage	Open	Accessible	Signs
Backflow Supply delta pod	Control	4"	Pad Locked	Ok	Ok	Ok	Ok
Backflow System Side	Control	4"	Pad Locked	Ok	Ok	Ok	Ok
Backflow Supply	Control	6"	Pad Locked	Ok	Ok	Ok	Ok
Backflow System Side	Control	6"	Pad Locked	Ok	Ok	Ok	Ok
Admin / Medical							
Admin-Medical	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok
Bravo pod							
Bravo.-Charlie pod closet	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok
Alpha Pod							
Riser Training office	Butterfly	4"	Supervised	Ok	Ok	Ok	Ok
Echo							
Echo-Charlie pod closet	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok
Charlie							
Charlie in Charlie closet	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok
Delta							
Delta- Charlie pod closet	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok
riser	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok
Sally Port							
Sally port Bus closet	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok
Ok - Passes Inspection S - Serviced on site X - Requires Service NA - Not Applicable							

Report of Inspection/Test

Quarterly Sprinkler

01/31/2018

Property: Okaloosa County Jail NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000006306

Deficiency / Recommendations Summary

These items were deficient and do not meet the requirements of the applicable code at the time of the inspection. Items marked *Recommendation* are not required by the applicable code but are opportunities to improve the Life Safety of the property.

Flow Test Delta Delta Pod

Central Dry System Riser Main drain Delta Pod

DELTA System/Location

MAINTENANCE

CHASE

SYSTEM IS CONTROLLED BY ADMIN/MEDICAL IN CHARLIE POD CLOSET. DRAIN IS NOT PIPED OUT OF ROOM 2 INCH VALVE ONL

Inspector's Test Valve Delta Delta Pod

Central Dry System Riser Main drain Delta Pod

No Alarm Reported?

Inspector's Test Valve Sally Port Sally Port

Dry System Riser OS&Y Sally Port

No Easily accessible?

NEED PIPED DOWN TO HEAD HIGH

Report of Inspection/Test

Annual Sprinkler

08/29/2019

Property

Okaloosa County
 Administrative Building NEW
 1250 Eglin Pkwy
 Shalimar, FL

Randy Overly
 (850)420-1267

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
 ALARMS - SPRINKLERS - EXTINGUISHERS

850-862-7812

Conducted by: Henry Jablonski

Inspection Ref: 200000010101

Print Date: 4/14/2020

Signatures

Inspector - Printed Henry Jablonski	Inspector - Signature 	Date Completed 8/29/19	I state that the information on this form is correct at the time and place of my inspection, and that all equipment tested at this time was left in operational condition upon completion of this inspection except as noted.
--	---------------------------	---------------------------	---

Tag Color

System Description/Location	Tag Color
Wet/Riser Mechanical Room	Green

Notifications

To Be Notified	Testing Time	Phone Test	Contact / Operator
Security Central	Start Time: 6:30	800-286-5699	Monitoring
	End Time: 1:00	800-286-5699	Monitoring
Okaloosa	Start Time: 6:30	850-689-5766	Dispatch
	End Time: 1:00	850-689-5766	Dispatch

Equipment Summary

Description	Site	Inspected		Unable to Inspect		Serviced Repaired		Failed		
	Qty	Qty	%	Qty	%	Qty	%	Qty	%	
Sprinkler Sectional CV - FT, ITV										
Inspector's test	2	2	100.0%	0	0.0%	0	0.0%	0	0.0%	
Butterfly	1	1	100.0%	0	0.0%	0	0.0%	0	0.0%	
Sprinkler Valve										
OS&Y	2	2	100.0%	0	0.0%	0	0.0%	0	0.0%	
Sprinkler Wet System Riser										
Main drain	1	1	100.0%	0	0.0%	0	0.0%	0	0.0%	

System Valve Inspection

Location/Description	Valve Description	Pressure Readings			Physical Condition	Pressures	Trim valves	Leakage	Hydraulic Sign	Valve Interior Inspection or Dry Valve Full Flow Test	
		Supply	System	Accelerator (if present)						Year Due	Inspection or Test Performed

Print Date: 4/14/2020

Page 1 of 3

Report of Inspection/Test

Annual Sprinkler

08/29/2019

Property: Okaloosa County Administrative Building NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000010101

System Valve Inspection

Location/Description	Valve Description	Pressure Readings			Physical Condition	Pressures	Trim valves	Leakage	Hydraulic Sign	Valve Interior Inspection or Dry Valve Full Flow Test	
		Supply	System	Accelerator (if present)						Year Due	Inspection or Test Performed
Wet/Riser Mechanical Room	4" Riser Check 2014 Central G	50	50	NA	Ok	Ok	Ok	Ok	Ok	2019	No

Fire Sprinklers

Sprinkler Type	Manufacturer Model	K Factor Temperature	Thread Size	Year of Manufacture	Year Replace or Testing Required	Replace Test or Recall Req Ok ?	Spare Sprinkler Available	Wrench Available
QR Pendent Chrome	Globe GL5601	5.6/155	1/2"	2014	2034	Yes	Yes	Yes
QR Sidewall White	Globe GL	5.6/155	1/2"	2014	2034	Yes	Yes	Yes
QR Upright Brass	Globe GL5615	5.6/200	1/2"	2014	2034	Yes	Yes	Yes

Pressure Gauge Inspection List

Qty	Location / Description	Condition Ok ?	Year Due for Replacement (5-Years)	Date Prior to Required Replacement ?	Quantity Replaced
2	Wet/Riser Mechanical Room	Yes	2019	Yes	0

Long Cycle Items

Item Type	Location/Description	Required Frequency	Last Performed	Next Due
Wet system	Riser/Building	5 Year	2015	2020

Pipe

Yes	In good condition ?	Yes	Free of mechanical damage and not leaking ?
Yes	No external corrosion ?	Yes	Properly aligned ?
Yes	No external loads ?	Yes	Visible pipe hangers and seismic braces not damaged or loose ?

Sprinklers

NA	Extra high, very extra high and ultra high temperature sprinklers tested ?	No	Eng evaluation recommended for spacing?
No	Eng evaluation recommended for sprinkler type?	Yes	Proper number and type of spare sprinklers?
Yes	Free of corrosion?	Yes	Free of obstructions to spray patterns?
Yes	Free of foreign materials including paint?	Yes	Free of physical damage?
Yes	Sprinklers free of loading and dirt?	Yes	Escutcheons and coverplates for recessed, flush and concealed sprinklers not missing?
Yes	Are all sprinklers in service dated 1920 or later?	Yes	Fast Response sprinklers in service for less than 20 years? If no test sample now and every 10 years.
Yes	Standard sprinklers less than 50 years old ? If no test sample now and every 10 years.	NA	If sprinklers have been replaced, were they proper replacements?

Report of Inspection/Test

Annual Sprinkler

08/29/2019

Property: Okaloosa County Administrative Building NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000010101

Fire Department Connection Wet/SW Corner Near Parking

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Flow Test

System	Connection Flowed	Outlet Size	Pressure (psi)			Time To Restore	Results comparable to prior test
			Static	Resid	Static		
Wet/Riser Mechanical Room	Inspector's test	1/2"	50	40	50	5	Yes
Wet/1st Floor SW Riser	Inspector's test	1/2"	60	40	45	10	Yes
Wet/2nd Floor SW Riser	Inspector's test	1/2"	40	30	40	10	Yes
Wet/3rd Floor SW Riser	Inspector's test	1/2"	40	35	40	10	Yes

Inspector's Test Valve

System/Location	Alarm Reported	Time to Alarm	Smooth Bore Orifice	Signage	Easily Accessible
Wet/Riser Mechanical Room	Yes	27	Yes	Yes	Yes
Wet/1st Floor SW Riser	Yes	70	Yes	Yes	Yes
Wet/2nd Floor SW Riser	Yes	32	Yes	Yes	Yes
Wet/3rd Floor SW Riser	Yes	34	Yes	Yes	Yes

Valve Inspection List

Location	Valve Type	Size	Secured	Inspection				Maint.			
				Leakage	Open	Accessible	Signs	Exercised	# of Turns	Lubricated	
Wet/Riser Mechanical Room	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok	Ok	Ok	9	NA
Wet/1st Floor SW Riser	Butterfly	4"	Supervised	Ok	Ok	Ok	Ok	Ok	Ok	12	NA
Wet/2nd Floor SW Riser	Butterfly	4"	Supervised	Ok	Ok	Ok	Ok	Ok	Ok	9	NA
Wet/3rd Floor SW Riser	Butterfly	4"	Supervised	Ok	Ok	Ok	Ok	Ok	Ok	9	NA
Backflow Supply	OS&Y	6"	Pad Locked	Ok	Ok	Ok	NA	NA	NA	20	NA
Backflow System Side	OS&Y	6"	Pad Locked	Ok	Ok	Ok	NA	NA	NA	20	NA

Ok - Passes Inspection S - Serviced on site X - Requires Service NA - Not Applicable

Report of Inspection/Test

Annual Sprinkler

10/01/2019

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS - SPRINKLERS - EXTINGUISHERS

850-862-7812

Property

Okaloosa County Courthouse
Annex Extension NEW
1940 Lewis Turner Blvd
Fort Walton Beach, FL 32548

Owner/Agent

Okaloosa Co. Facility
Maintenance
5489 Old Bethel Road
Crestview, FL 32536

Conducted by: David Woodard

Inspection Ref: 200000010431

Randy Overly
(850)420-1267

(850)830-1600

Print Date: 4/14/2020

Signatures

Inspector - Printed Eric Frongner	Inspector - Signature 	Date Completed 10/2/19	I state that the information on this form is correct at the time and place of my inspection, and that all equipment tested at this time was left in operational condition upon completion of this inspection except as noted.
Owner's Representative - Prin Gary Madden	Owner's Representative - Signatu 	Date Completed 10/2/19	Except as noted, the building is occupied with the same occupancy classification and hazard of contents as last inspection. Also, the system has remained in service without modification and been free of actuation of devices or alarms.

Tag Color

System Description/Location	Tag Color
Wet System	
Wet/Riser Loading Dock	Green
Wet/ Fire Pump Room Outside	Yellow-Non critical
Dry System	
Dry/Riser Loading Dock	Yellow-Non critical

Notifications

To Be Notified	Testing Time	Phone Test	Contact / Operator
Security Central	Start Time: 0545	800-286-5699	Chris
	End Time: 8:45	800-286-5699	Chris
Okaloosa Dispatch	Start Time: 0545	850-689-5766	Heather
	End Time: 8:45	850-689-5766	Heather

Equipment Summary

Description	Site	Inspected		Unable to Inspect		Serviced Repaired		Failed		
	Qty	Qty	%	Qty	%	Qty	%	Qty	%	
Sprinkler Dry System Riser										
Main drain	1	1	100.0%	0	0.0%	0	0.0%	0	0.0%	
Sprinkler Gauges										
	1	1	100.0%	0	0.0%	0	0.0%	0	0.0%	
Sprinkler Hose Valve Outlets										
	3	3	100.0%	0	0.0%	0	0.0%	0	0.0%	

Print Date: 4/14/2020

Page 1 of 10

Report of Inspection/Test

Annual Sprinkler

10/01/2019

Property: Okaloosa County Courthouse Annex Extensior

Owner: Okaloosa Co. Facility Maintenance

Inspection Ref: 20000010431

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Equipment Summary

Description	Site	Inspected		Unable to Inspect		Serviced Repaired		Failed	
	Qty	Qty	%	Qty	%	Qty	%	Qty	%
Sprinkler Pump									
Butterfly	1	1	100.0%	0	0.0%	0	0.0%	0	0.0%
Sprinkler Sectional CV - FT, ITV									
Inspector's test	2	2	100.0%	0	0.0%	0	0.0%	0	0.0%
Sprinkler Valve									
OS&Y	2	2	100.0%	0	0.0%	0	0.0%	0	0.0%
Sprinkler Wet System Riser									
Inspector's test	1	1	100.0%	0	0.0%	0	0.0%	0	0.0%

System Valve Inspection

Location/Description	Valve Description	Pressure Readings			Physical Condition	Pressures	Trim valves	Leakage	Hydraulic Sign	Valve Interior Inspection or Dry Valve Full Flow Test	
		Supply	System	Accelerator (if present)						Year Due	Inspection or Test Performed
Wet System											
Wet/Riser Loading Dock	3"			NA	Ok	Ok	Ok	Ok	Ok	2023	No

Fire Sprinklers

Sprinkler Type	Manufacturer Model	K Factor Temperature	Thread Size	Year of Manufacture	Year Replace or Testing Required	Replace Test or Recall Req Ok ?	Spare Sprinkler Available	Wrench Available
QR Pendent Chrome	Viking VK302	155	1/2"	2011	2031	Yes	Yes	Yes
QR Concealed White	Viking VK462	155	1/2"	2011	2031	Yes	Yes	Yes
QR Upright Brass	Tyco TY3131	200	1/2"	2010	2030	Yes	Yes	Yes

Pressure Gauge Inspection List

Qty	Location / Description	Condition Ok ?	Year Due for Replacement (5-Years)	Date Prior to Required Replacement ?	Quantity Replaced
Wet System					
1	Wet/Riser Loading Dock	Yes	2023	Yes	0
5	Wet/ Fire Pump Room Outside	Yes	2023	Yes	0
Dry System					
2	Dry/Riser Loading Dock	Yes	2023	Yes	0

Report of Inspection/Test

Annual Sprinkler

10/01/2019

Property: Okaloosa County Courthouse Annex Extensior

Owner: Okaloosa Co. Facility Maintenance

Inspection Ref: 200000010431

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Long Cycle Items

Item Type	Location/Description	Required Frequency	Last Performed	Next Due
Riser	All of building	Every 5 years	8/9/2018	8/2023
Pipe				
Yes	In good condition ?	Yes	Free of mechanical damage and not leaking ?	
Yes	No external corrosion ?	Yes	Properly aligned ?	
Yes	No external loads ?	Yes	Visible pipe hangers and seismic braces not damaged or loose ?	
Sprinklers				
NA	Extra high, very extra high and ultra high temperature sprinklers tested ?	No	Eng evaluation recommended for spacing?	
No	Eng evaluation recommended for sprinkler type?	Yes	Proper number and type of spare sprinklers?	
Yes	Free of corrosion?	Yes	Free of obstructions to spray patterns?	
Yes	Free of foreign materials including paint?	Yes	Free of physical damage?	
Yes	Sprinklers free of loading and dirt?	Yes	Escutcheons and coverplates for recessed, flush and concealed sprinklers not missing?	
Yes	Are all sprinklers in service dated 1920 or later?	Yes	Fast Response sprinklers in service for less than 20 years? If no test sample now and every 10 years.	
Yes	Standard sprinklers less than 50 years old ? If no test sample now and every 10 years.	Yes	If sprinklers have been replaced, were they proper replacements?	
Cold Weather Check Dry/Riser Loading Dock Dry System				
Yes	Adequate heat in areas with wet piping?	NA	Low temperature alarms in dry pipe, preaction and deluge valve enclosures functioning?	
Yes	Interior of pipe in preaction and dry pipe systems which passes through freezers free of ice blockage?	Yes	Low points drained in dry pipe, preaction and deluge systems prior to the onset of freezing weather?	
Fire Department Connection Wet/Front Parking Lot Wet System				
Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?	
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?	
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?	
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?	
NA	Valve clapper operational over its full range (if caps are not in place) ?			
Hose Valve Outlets Stair 4 Wet Standpipe				
Yes	Caps, hose connections, valve handle, cap gasket, restricting devices in place, undamaged and in good condition ?	Yes	Valves not leaking and no visible obstructions ?	
Hose Valve Outlets Stair 2 Wet Standpipe				
Yes	Caps, hose connections, valve handle, cap gasket, restricting devices in place, undamaged and in good condition ?	Yes	Valves not leaking and no visible obstructions ?	
Hose Valve Outlets Stair 3 Wet Standpipe				
Yes	Caps, hose connections, valve handle, cap gasket, restricting devices in place, undamaged and in good condition ?	Yes	Valves not leaking and no visible obstructions ?	

Report of Inspection/Test

Annual Sprinkler

10/01/2019

Property: Okaloosa County Courthouse Annex Extensior

Owner: Okaloosa Co. Facility Maintenance

Inspection Ref: 200000010431

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Fire Pump Electric Inspection Wet System

Yes	Pump house/room at least 40deg F?	Yes	Suction, discharge and bypass valves open?
Yes	Piping free from leaks?	Yes	Suction and system pressure gauges normal?
NA	Suction reservoir, if provided, full?	Yes	Controller indicating power ON ?
Yes	Transfer switch indicating normal situation?	Yes	Isolation switch closed?
Yes	Reverse phase alarm indicator OFF or normal phase rotation indicator ON ?	Yes	Circulation relief valve flowing water while pump churns?
Yes	Pressure relief valves operating with proper pressure downstream while pump is operational?		

Fire Pump Electric Test Wet System

Yes	Pump started automatically?	85	Record starting pressure.
85	Record starting pressure.	130	Pump shutoff pressure.
110	Jockey pump shutoff pressure.	95	Jockey pump starting pressure.
Yes	Pump run for at least 10 minutes?	45	Record suction pressure while running.
130	Record discharge pressure while running.	Yes	Pump packing gland showing slight discharge? (Adjust if necessary)
Yes	Free from unusual noises or vibrations?	Yes	Packing boxes, bearings and pump casing free from overheating?
3	Record time for motor to accelerate to full speed.	1	For reduced voltage or reduced current starting, record time controller is on first step.
10	For automatic stop controllers, record time pump runs after starting.	Yes	All times and pressures acceptable?
Have to turn off			
No auto stop			

Fire Pump Electric Maintenance Wet System

NA	Changed pump bearing lubrication?	NA	Shaft end play acceptable?
NA	Pump coupling alignment acceptable?	NA	Transmission coupling, right angle gear drive and mechanical moving parts lubricated?
NA	Circuit breakers passed trip test?	NA	Emergency manual starting means operated without power?
NA	Electrical connections secure?	NA	Pressure switch settings calibrated?
NA	Motor bearings greased?	NA	Control and power wirings tight?
NA	Isolation switch and circuit breaker exercised?	NA	Circuit breakers appear clean?
NA	Electrical system free of wire chafing?	NA	Manual starting means on electrical systems operated?
NA	Boxes, panels and cabinets on electrical systems cleaned?	NA	Isolation switch and circuit breaker exercised?
NA	Circuit breakers appear clean?		

Report of Inspection/Test

Annual Sprinkler

10/01/2019

Property: Okaloosa County Courthouse Annex Extensior

Owner: Okaloosa Co. Facility Maintenance

Inspection Ref: 200000010431

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Fire Pump Electric Flow Test Wet System

Yes	Pump test run by discharge of flow through hose streams. Flow readings were taken at each hose stream.		Pump test run by discharge through by-pass flow meter to drain or suction reservoir. Flow readings taken by flow meter.
	Pump test run by discharge through by-pass flow meter directly returned to pump suction. Flow readings taken by flow meter.	Yes	Are the pressure readings acceptable?
NA	No-flow (churn) test run for 30 min?	Yes	Circulation relief valve and pressure relief valve operated properly during all flow tests?
Yes	No alarm indicators or other visible abnormalities observed during no-flow test?		Low suction throttling device test: Low suction pressure simulated?
	Low suction throttling device test: Free from abnormalities in throttling action?		Low suction throttling device test: Free from abnormalities in return to full flow?
	Automatic transfer switch test: Power failure simulated during peak flow?		Automatic transfer switch test: Connection made to alternate power source?
	Automatic transfer switch test: After termination of simulated power failure did motor reconnect to the normal power source?		All alarm conditions simulated?
Yes	All alarms operated?		

Flow Test

System	Connection Flowed	Outlet Size	Pressure (psi)			Time To Restore	Results comparable to prior test
			Static	Resid	Static		
Wet System							
Wet/Riser Loading Dock	Main drain	2	110	70	110	15	Yes
Wet/2nd Floor Stair 3	Inspector's test	1/2	90	70	90	20	Yes
Wet/3rd Floor Stair 3	Inspector's test	1/2	85	65	85	15	Yes
Dry System							
Dry/Riser Loading Dock	Main drain	1-1/2"	55	40	55	10	Yes

Inspector's Test Valve

System/Location	Alarm Reported	Time to Alarm	Smooth Bore Orifice	Signage	Easily Accessible
Wet System					
Wet/Riser Loading Dock	Yes	30	Yes	Yes	Yes
Wet/2nd Floor Stair 3	Yes	32	Yes	Yes	Yes
Wet/3rd Floor Stair 3	Yes	42	Yes	Yes	Yes
Dry System					
Dry/Riser Loading Dock	Yes	40	Yes	Yes	Yes

Valve Inspection List

Report of Inspection/Test

Annual Sprinkler

10/01/2019

Property: Okaloosa County Courthouse Annex Extensior

Owner: Okaloosa Co. Facility Maintenance

Inspection Ref: 200000010431

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Valve Inspection List

Location	Valve Type	Size	Secured	Inspection				Maint.			
				Leakage	Open	Accessible	Signs	Exercised	# of Turns	Lubricated	
Wet System											
Wet/Riser Loading Dock	Butterfly	3"	Supervised	Ok	Ok	Ok	Ok	Ok	8	Ok	
Wet/2nd Floor Stair 3	Butterfly	3"	Supervised	Ok	Ok	Ok	Ok	Ok	16	NA	
Wet/3rd Floor Stair 3	Butterfly	3"	Supervised	Ok	Ok	Ok	Ok	Ok	16	NA	
Wet/ Fire Pump Room Outside	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok	Ok	15	NA	
Wet/ Fire Pump Room Outside	Butterfly	4"	Supervised	Ok	Ok	Ok	Ok	Ok	15	NA	
Wet/ Fire Pump Room Outside	Butterfly	4"	Supervised	Ok	Ok	Ok	Ok	Ok	15	NA	
Tamper switch failed to report to panel											
Wet/ Fire Pump Room Outside	Butterfly	4"	Supervised	Ok	Ok	Ok	Ok	Ok	15	NA	
Dry System											
Dry/Riser Loading Dock	Butterfly	3"	Supervised	Ok	Ok	Ok	Ok	Ok	10	Ok	
Backflow Supply											
Backflow Street Entrance	OS&Y	6"	Pad Locked	Ok	Ok	Ok	Ok	Ok	0	Ok	
Backflow System Side											
Backflow Street Entrance	OS&Y	6"	Pad Locked	Ok	Ok	Ok	Ok	Ok	0	Ok	
Ok - Passes Inspection S - Serviced on site X - Requires Service NA - Not Applicable											

Dry Valve Trip Test - Dry System

Dry Valve		Size: 3"	Year:	Q. O. D.		Year:
Make	Model	Serial no.	Make	Model	Serial no.	
Viking	DV/1					
	Time to Trip thru test pipe	Water Pressure	Air Pressure	Trip point air pressure	Time water reached test outlet	Alarm Operated
Without Q.O.D.	40 sec	80 psi	35 psi	10 psi	50 sec	Yes
With Q.O.D.	sec	psi	psi	psi	sec	

Comparable to previous tests ?

PS10 Potter alarm switch stays in alarm and is now bypassed

Print Date: 4/14/2020

Page 6 of 10

Report of Inspection/Test

Annual Sprinkler

10/01/2019

Property: Okaloosa County Courthouse Annex Extensior

Owner: Okaloosa Co. Facility Maintenance

Inspection Ref: 200000010431

B&C FIRE SAFETYFIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS**850-862-7812***Pump Equipment/Component Summary*

Item	Manufacturer	Model	Serial No.
	Location / Description		
Wet System			
Fire Pump	Patterson	5X3 VIP	FP-C098290
	30 psi 500 gpm	Centrifugal	
Motor			
	30 HP 3540 RPM	200 VAC 60 cycles	
Fire Pump Controller	Eaton	FT90-30D-L1	16BL664E
Jockey Pump	Grundfos	CR-1	
Jockey Pump Controller	Eaton	FDJP-0.75D	16BL664J

Report of Inspection/Test

Annual Sprinkler

10/01/2019

Property: Okaloosa County Courthouse Annex Extensior

Owner: Okaloosa Co. Facility Maintenance

Inspection Ref: 200000010431

B&C FIRE SAFETY




FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

PUMPD Test Point with Stream Detail

Flow (measured)		Pressure (measured)			Speed (rpm)
% Rated	Flow	Net	Suction	Discharge	
Churn	0	100	35	135	3,546
100%	502	100	30	130	3,535
151%	753	95	25	120	3,519

Performance Graph



Report of Inspection/Test

Annual Sprinkler

10/01/2019

Property: Okaloosa County Courthouse Annex Extensior

Owner: Okaloosa Co. Facility Maintenance

Inspection Ref: 200000010431

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Fire Pump Flow Test Stream Detail

Flow	Stream 1		Stream 2		Stream 3		Stream 4		Stream 5		Stream 6	
	Pitot	Flow										
	Orifice											
gpm	C		C		C		C		C		C	
0	1.75		1.75		1.75		1.75		1.75		1.75	
	1		1		1		1		1		1	
100%	8	251	8	251								
	1.75		1.75		1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75
502	1		1		1	1	1	1	1	1	1	1
151%	18	376	18	376								
	1.75		1.75		1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75
753	1		1		1	1	1	1	1	1	1	1

Report of Inspection/Test

Annual Sprinkler

10/01/2019

Property: Okaloosa County Courthouse Annex Extensior

Owner: Okaloosa Co. Facility Maintenance

Inspection Ref: 200000010431

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Deficiency / Recommendations Summary

These items were deficient and do not meet the requirements of the applicable code at the time of the inspection. Items marked *Recommendation* are not required by the applicable code but are opportunities to improve the Life Safety of the property.

Dry Pipe Valve Test With QOD Dry System Dry/Riser Loading Dock

Viking DV/1 Dry System Riser Main drain Dry/Riser Loading Dock

Yes Alarm operate ? No QOD

PS10 Potter alarm switch stays in alarm and is now bypassed

Fire Pump Electric Test Wet System Wet/ Fire Pump Room Outside

Patterson 5X3 VIP Pump ButterflyFP-C098290 Wet/ Fire Pump Room Outside

10 For automatic stop controllers, record time pump runs after starting.

Have to turn off

No auto stop

NFPA 25-2002 8.3.2.2(2)(c) *Electrical System Procedure. (c) Record the time pump runs after starting (for automatic stop controllers).*

Control Valve Bypass Supply Wet System Wet/ Fire Pump Room Outside

Patterson 5X3 VIP Pump ButterflyFP-C098290 Wet/ Fire Pump Room Outside

Supervised Secured ?

Tamper switch failed to report to panel

NFPA 25-2002 12.3.2.2(1) *The valve inspection shall verify that the valves are in the following condition: (a) In the normal open or closed position*

Report of Inspection/Test

Annual Sprinkler

06/28/2019

Property

Okaloosa County EMS NEW

714 Essex Rd.

Fort Walton Beach, FL 32547

Arron Hall

850-460-0093

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS - SPRINKLERS - EXTINGUISHERS

850-862-7812

Conducted by: Henry Jablonski

Inspection Ref: 200000009692

Print Date: 4/14/2020

Signatures

Inspector - Printed Henry Jablonski	Inspector - Signature 	Date Completed 6/28/19	I state that the information on this form is correct at the time and place of my inspection, and that all equipment tested at this time was left in operational condition upon completion of this inspection except as noted.
--	---------------------------	---------------------------	---

Tag Color

System Description/Location	Tag Color
Wet System	
Wet riser Storeroom	Green

Notifications

To Be Notified	Testing Time	Phone Test	Contact / Operator
Security Central	Start Time: 3:15	800 286-5699	Monitoring
	End Time: 4:15	800 286-5699	Monitoring
Okaloosa County	Start Time: 3:15	850-689-5766	Dispatch
	End Time: 4:15	850-689-5766	Dispatch

Equipment Summary

Description	Site	Inspected		Unable to Inspect		Serviced Repaired		Failed		
	Qty	Qty	%	Qty	%	Qty	%	Qty	%	
Sprinkler Valve										
OS&Y	2	2	100.0%	0	0.0%	0	0.0%	0	0.0%	
Sprinkler Wet System Riser										
	1	1	100.0%	0	0.0%	0	0.0%	0	0.0%	

System Valve Inspection

Location/Description	Valve Description	Pressure Readings			Physical Condition	Pressures	Trim valves	Leakage	Hydraulic Sign	Valve Interior Inspection or Dry Valve Full Flow Test	
		Supply	System	Accelerator (if present)						Year Due	Inspection or Test Performed
Wet System											
Wet riser Storeroom	3"			NA	Ok	Ok	Ok	Ok	Ok	2021	No

Print Date: 4/14/2020

Page 1 of 3

Report of Inspection/Test

Annual Sprinkler

06/28/2019

Property: Okaloosa County EMS NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000009692

Fire Sprinklers

Sprinkler Type	Manufacturer Model	K Factor Temperature	Thread Size	Year of Manufacture	Year Replace or Testing Required	Replace Test or Recall Req Ok ?	Spare Sprinkler Available	Wrench Available
QR Upright Brass	Victaulic V2704	5.6/165	1/2"	2010	2030	Yes	Yes	Yes
Std Upright Brass	Victaulic V2703	5.6/165	1/2"	2011	2031	Yes	Yes	Yes
QR Pendent Chrome	Victaulic V2708	5.6/155	1/2"	2011	2031	Yes	Yes	Yes

Pressure Gauge Inspection List

Qty	Location / Description	Condition Ok ?	Year Due for Replacement (5-Years)	Date Prior to Required Replacement ?	Quantity Replaced
Wet System					
1	Wet riser Storeroom	Yes	2023	Yes	0

Long Cycle Items

Item Type	Location/Description	Required Frequency	Last Performed	Next Due
Wet system	Riser/Building	5 year		Now

Pipe

Yes	In good condition ?	Yes	Free of mechanical damage and not leaking ?
Yes	No external corrosion ?	Yes	Properly aligned ?
Yes	No external loads ?	Yes	Visible pipe hangers and seismic braces not damaged or loose ?

Sprinklers

NA	Extra high, very extra high and ultra high temperature sprinklers tested ?	No	Eng evaluation recommended for spacing?
No	Eng evaluation recommended for sprinkler type?	Yes	Proper number and type of spare sprinklers?
Yes	Free of corrosion?	Yes	Free of obstructions to spray patterns?
Yes	Free of foreign materials including paint?	Yes	Free of physical damage?
Yes	Sprinklers free of loading and dirt?	Yes	Escutcheons and coverplates for recessed, flush and concealed sprinklers not missing?
Yes	Are all sprinklers in service dated 1920 or later?	Yes	Fast Response sprinklers in service for less than 20 years? If no test sample now and every 10 years.
Yes	Standard sprinklers less than 50 years old ? If no test sample now and every 10 years.	NA	If sprinklers have been replaced, were they proper replacements?

Fire Department Connection Front of Bldg Wet System

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Flow Test

Print Date: 4/14/2020

Page 2 of 3

Report of Inspection/Test

Annual Sprinkler

06/28/2019

Property: Okaloosa County EMS NEW

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000009692

Flow Test

System	Connection Flowed	Outlet Size	Pressure (psi)			Time To Restore	Results comparable to prior test
			Static	Resid	Static		
<i>Wet System</i>							
Wet riser Storeroom	Inspector's test	2	55	45	50	5	Yes

Inspector's Test Valve

System/Location	Alarm Reported	Time to Alarm	Smooth Bore Orifice	Signage	Easily Accessible
<i>Wet System</i>					
Wet riser Storeroom	Yes	32	Yes	Yes	Yes

Valve Inspection List

Location	Valve Type	Size	Secured	Inspection				Maint.			
				Leakage	Open	Accessible	Signs	Exercised	# of Turns	Lubricated	
<i>Wet System</i>											
Wet riser Storeroom	OS&Y	3"	Supervised	Ok	Ok	Ok	Ok	Ok	Ok	17	NA
<i>Backflow Supply</i>											
Riser	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok	Ok	Ok	14	NA
<i>Backflow System Side</i>											
Riser	OS&Y	4"	Supervised	Ok	Ok	Ok	Ok	Ok	Ok	14	NA

Ok - Passes Inspection S - Serviced on site X - Requires Service NA - Not Applicable

Report of Inspection/Test

Annual Sprinkler

11/20/2019

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS - SPRINKLERS - EXTINGUISHERS

850-862-7812

Property

Okaloosa County Health
Department Crestview NEW
810 East James Lee Blvd.
Crestview, FL 32536

Owner/Agent

Okaloosa Co. Facility
Maintenance
5489 Old Bethel Road
Crestview, FL 32536

Conducted by: Henry Jablonski

Inspection Ref: 200000010535

John Alfone
(850)833-9240 x2255

Randy Overly
(850)420-1267

Print Date: 4/14/2020

Signatures

Inspector - Printed Eric Frongner	Inspector - Signature 	Date Completed 11/20/19	I state that the information on this form is correct at the time and place of my inspection, and that all equipment tested at this time was left in operational condition upon completion of this inspection except as noted.
--------------------------------------	---------------------------	----------------------------	---

Tag Color

System Description/Location	Tag Color
Riser	Green

Notifications

To Be Notified	Testing Time	Phone Test	Contact / Operator
Security Central	Start Time: 615	800-286-5699	Monitoring
	End Time: 900	800-286-5699	Monitoring
City of Crestview	Start Time: 615	850-682-3741	Dispatch
	End Time: 900	850-682-3741	Dispatch

Equipment Summary

Description	Site	Inspected		Unable to Inspect		Serviced Repaired		Failed	
	Qty	Qty	%	Qty	%	Qty	%	Qty	%
Sprinkler Wet System Riser									
Riser Check	1	1	100.0%	0	0.0%	0	0.0%	0	0.0%

System Valve Inspection

Location/Description	Valve Description	Pressure Readings			Physical Condition	Pressures	Trim valves	Leakage	Hydraulic Sign	Valve Interior Inspection or Dry Valve Full Flow Test	
		Supply	System	Accelerator (if present)						Year Due	Inspection or Test Performed
Riser	4" Riser Check Victaulic	65	75	NA	Ok	Ok	Ok	Ok	Ok	2020	No

Print Date: 4/14/2020

Page 1 of 3

Report of Inspection/Test

Annual Sprinkler

11/20/2019

Property: Okaloosa County Health Department Crestview

Owner: Okaloosa Co. Facility Maintenance

Inspection Ref: 20000010535

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Fire Sprinklers

Sprinkler Type	Manufacturer Model	K Factor Temperature	Thread Size	Year of Manufacture	Year Replace or Testing Required	Replace Test or Recall Req Ok ?	Spare Sprinkler Available	Wrench Available
Std Pendent	Central Solder link	5.6/155	1/2"			Yes	Yes	Yes

Pressure Gauge Inspection List

Qty	Location / Description	Condition Ok ?	Year Due for Replacement (5-Years)	Date Prior to Required Replacement ?	Quantity Replaced
2	Riser	Yes	2020	Yes	0

Long Cycle Items

Item Type	Location/Description	Required Frequency	Last Performed	Next Due
Wet system	All	5 year	2015	2020

Pipe

Yes	In good condition ?	Yes	Free of mechanical damage and not leaking ?
Yes	No external corrosion ?	Yes	Properly aligned ?
Yes	No external loads ?	Yes	Visible pipe hangers and seismic braces not damaged or loose ?

Sprinklers

NA	Extra high, very extra high and ultra high temperature sprinklers tested ?	No	Eng evaluation recommended for spacing?
No	Eng evaluation recommended for sprinkler type?	Yes	Proper number and type of spare sprinklers?
Yes	Free of corrosion?	Yes	Free of obstructions to spray patterns?
Yes	Free of foreign materials including paint?	Yes	Free of physical damage?
Yes	Sprinklers free of loading and dirt?	Yes	Escutcheons and coverplates for recessed, flush and concealed sprinklers not missing?
Yes	Are all sprinklers in service dated 1920 or later?	Yes	Fast Response sprinklers in service for less than 20 years? If no test sample now and every 10 years.
Yes	Standard sprinklers less than 50 years old ? If no test sample now and every 10 years.	NA	If sprinklers have been replaced, were they proper replacements?

Fire Department Connection

Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?
NA	Valve clapper operational over its full range (if caps are not in place) ?		

Flow Test

System	Connection Flowed	Outlet Size	Pressure (psi)			Time To Restore	Results comparable to prior test
			Static	Resid	Static		
Riser	Inspector's test	2	75	55	70	10	Yes

Print Date: 4/14/2020

Page 2 of 3

Report of Inspection/Test

Annual Sprinkler

11/20/2019

Property: Okaloosa County Health Department Crestview

Owner: Okaloosa Co. Facility Maintenance

Inspection Ref: 20000010535

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspector's Test Valve

System/Location	Alarm Reported	Time to Alarm	Smooth Bore Orifice	Signage	Easily Accessible
Riser	Yes	42	Yes	Yes	Yes

Valve Inspection List

Location	Valve Type	Size	Secured	Inspection				Maint.			
				Leakage	Open	Accessible	Signs	Exercised	# of Turns	Lubricated	
Riser	Butterfly	4"	Supervised	Ok	Ok	Ok	Ok	Ok	12	NA	
Backflow Supply	OS&Y	6"	Pad Locked	Ok	Ok	Ok	NA	NA	0	NA	
Backflow System Side	OS&Y	6"	Pad Locked	Ok	Ok	Ok	NA	NA	0	NA	

Ok - Passes Inspection S - Serviced on site X - Requires Service NA - Not Applicable

Report of Inspection/Test

Annual Sprinkler

04/03/2020

Property

Okaloosa County Health
 Department FWB NEW
 221 Hospital Dr.
 Fort Walton Beach, FL 32547

John Alfone
 (850)833-9240 x2255

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
 ALARMS - SPRINKLERS - EXTINGUISHERS

850-862-7812

Conducted by: Eric Frongner

Inspection Ref: 200000011285

Print Date: 4/14/2020

Signatures

Inspector - Printed Henry Jablonski	Inspector - Signature 	Date Completed 4/3/20	I state that the information on this form is correct at the time and place of my inspection, and that all equipment tested at this time was left in operational condition upon completion of this inspection except as noted.
--	---------------------------	--------------------------	---

Tag Color

System Description/Location	Tag Color
Wet system	
Wet riser	Green

Notifications

To Be Notified	Testing Time	Phone Test	Contact / Operator
Security Central	Start Time: 6:00	800-286-5699	Monitoring
	End Time: 9:00	800-286-5699	Monitoring
Okaloosa Dispatch	Start Time: 6:00	850-689-5766	Dispatch
	End Time: 9:00	850-689-5766	Dispatch

Equipment Summary

Description	Site	Inspected		Unable to Inspect		Serviced Repaired		Failed	
	Qty	Qty	%	Qty	%	Qty	%	Qty	%
Sprinkler Valve									
OS&Y	2	2	100.0%	0	0.0%	0	0.0%	0	0.0%
Sprinkler Wet System Riser									
OS&Y	1	1	100.0%	0	0.0%	0	0.0%	0	0.0%

System Valve Inspection

Location/Description	Valve Description	Pressure Readings			Physical Condition	Pressures	Trim valves	Leakage	Hydraulic Sign	Valve Interior Inspection or Dry Valve Full Flow Test	
		Supply	System	Accelerator (if present)						Year Due	Inspection or Test Performed
Wet system											
Wet riser	4"	NA	65	NA	Ok	Ok	Ok	Ok	Ok	2021	No

Print Date: 4/14/2020

Report of Inspection/Test

Annual Sprinkler

04/03/2020

Property: Okaloosa County Health Department FWB NE

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000011285

Fire Sprinklers

Sprinkler Type	Manufacturer Model	K Factor Temperature	Thread Size	Year of Manufacture	Year Replace or Testing Required	Replace Test or Recall Req Ok ?	Spare Sprinkler Available	Wrench Available
Sdt Pendent Chrome	Star SSP 735A	Sauder	1/2"	1992	2042	Yes	Yes	Yes
QR Pendent Chrome	Victaulic V2708	5.6/155	1/2"	2013	2033	Yes	Yes	Yes
QR Sidewall Chrome	Globe J90	155	1/2"	2013	2033	Yes	Yes	Yes
Std Upright Brass	Rasco SSUD1	212 sauder	1/2"	1992	2042	Yes	Yes	Yes

Pressure Gauge Inspection List

Qty	Location / Description	Condition Ok ?	Year Due for Replacement (5-Years)	Date Prior to Required Replacement ?	Quantity Replaced
Wet system					
1	Wet riser	Yes	2021	Yes	0

Long Cycle Items

Item Type	Location/Description	Required Frequency	Last Performed	Next Due
Riser	Riser Room	5 year	2016	2021

Pipe				
Yes	In good condition ?	Yes	Free of mechanical damage and not leaking ?	
Yes	No external corrosion ?	Yes	Properly aligned ?	
Yes	No external loads ?	Yes	Visible pipe hangers and seismic braces not damaged or loose ?	

Sprinklers				
NA	Extra high, very extra high and ultra high temperature sprinklers tested ?	No	Eng evaluation recommended for spacing?	
No	Eng evaluation recommended for sprinkler type?	Yes	Proper number and type of spare sprinklers?	
Yes	Free of corrosion?	Yes	Free of obstructions to spray patterns?	
Yes	Free of foreign materials including paint?	Yes	Free of physical damage?	
Yes	Sprinklers free of loading and dirt?	Yes	Escutcheons and coverplates for recessed, flush and concealed sprinklers not missing?	
Yes	Are all sprinklers in service dated 1920 or later?	Yes	Fast Response sprinklers in service for less than 20 years? If no test sample now and every 10 years.	
Yes	Standard sprinklers less than 50 years old ? If no test sample now and every 10 years.	Yes	If sprinklers have been replaced, were they proper replacements?	

Fire Department Connection NW Side of Bldg				
Yes	Visible and accessible?	Yes	Couplings and swivels not damaged and rotate smoothly?	
Yes	Plugs or caps in place and undamaged?	Yes	Gaskets in place and in good condition?	
Yes	Identification sign(s) in place?	Yes	Check valve is not leaking?	
Yes	Automatic drain valve in place and operating properly?	NA	Interior free of obstructions (if caps are not in place) ?	
NA	Valve clapper operational over its full range (if caps are not in place) ?			

Flow Test

Print Date: 4/14/2020

Page 2 of 3

Report of Inspection/Test

Annual Sprinkler

04/03/2020

Property: Okaloosa County Health Department FWB NE1

B&C FIRE SAFETY



FIRE SUPPRESSION SPECIALISTS
ALARMS • SPRINKLERS • EXTINGUISHERS

850-862-7812

Inspection Ref: 20000011285

Flow Test

System	Connection Flowed	Outlet Size	Pressure (psi)			Time To Restore	Results comparable to prior test
			Static	Resid	Static		
<i>Wet system</i>							
Wet riser	Main drain	2"	65	55	65	5	Yes

Inspector's Test Valve

System/Location	Alarm Reported	Time to Alarm	Smooth Bore Orifice	Signage	Easily Accessible
<i>Wet system</i>					
Wet riser	Yes	55	Yes	Yes	Yes

Valve Inspection List

Location	Valve Type	Size	Secured	Inspection				Maint.			
				Leakage	Open	Accessible	Signs	Exercised	# of Turns	Lubricated	
<i>Wet system</i>											
Wet riser	OS&Y	6"	Pad Locked	Ok	Ok	Ok	Ok	Ok	Ok	12	NA
Backflow Supply	OS&Y	6"	Pad Locked	Ok	Ok	Ok	NA	Ok	Ok	18	NA
Backflow System Side	OS&Y	6"	Pad Locked	Ok	Ok	Ok	NA	Ok	Ok	18	NA

Ok - Passes Inspection S - Serviced on site X - Requires Service NA - Not Applicable